

2047 -01-01

EPA REGION-9 SUPERFUND RECORDS CENTER



2047-00101

WASTE DISPOSAL INC

PROPERTY OF EPA REGION 9

HAZARDOUS WASTE MANAGEMENT DIVISION



**PLEASE RETURN TO RECORDS CENTER
215 FREMONT STREET
SAN FRANCISCO, CALIFORNIA 94105**

POOR LEGIBILITY

ONE OR MORE PAGES IN THIS DOCUMENT ARE DIFFICULT TO READ
DUE TO THE QUALITY OF THE ORIGINAL

AR0048

STATE OF CALIFORNIA

OFFICE MEMO
STD. 100 (REV. 11-75)

DATE _____

TO: _____

ROOM NUMBER _____

FROM: _____

PHONE NUMBER _____

SUBJECT: _____

City Council 2 Aug 83
David Moon with revised data

X NE corner for Phil Campbell
Should read NW corner.
data from Mr. George Beatty
Santa Fe Springs
Concern Planning Dept
Sept 83

Several abandoned site projects

FOUNDATION INVESTIGATION

Scope

This report presents the results and recommendations of our foundation investigation for the proposed commercial/industrial park to be located on approximately 4.8 acres of land at the northeast corner of Greenleaf Avenue and Los Nietos Road in Santa Fe Springs, California. The subject property encompasses Lot 1 of Tentative Parcel No. 14608. The preliminary development concept envisions the construction of light, concrete tilt-up structures along with access roads and parking areas.

* Planning Dept
S.F. Springs
says this
should be
northwest
corner.

The purpose of the study was to determine general soil conditions at the site and provide recommendations for foundation design, site grading, and design of flexible pavement sections.

The investigation included site inspection, test borings, laboratory testing, and engineering calculations. The work was authorized by Mr. David H. Van of Castille Builders, Ltd., representing the client.

Structural Considerations

Initial estimates of structural loads were not available at the time of writing this report. Consequently, for purposes of analysis, it was assumed that the maximum dead plus live load on columns would be less than 30 kips. We also assumed that none of the proposed buildings will have basements and that finished grade will be at or near to existing grade.



Field Investigation

The field investigation was completed in July, 1981 and included drilling eleven, 16-inch diameter bucket auger borings to depths ranging from 11 to 16 feet and excavating one shallow 2-foot deep test pit by hand. Details pertaining to the drilling operations are given on the Test Boring Logs, pages A-1 through A-6 in Appendix A. Boring locations are shown on the attached plan, page A-7.

Both bulk and undisturbed soil samples were obtained from the borings for laboratory testing. The undisturbed samples were obtained by means of a 2.5-inch I.D., thin wall sampler driven with a 1500 pound weight dropping approximately 12 inches. Sample depths and penetration rates are shown on the Test Boring Logs.

The drilling and sampling operations were performed under the direct supervision of an engineering geologist, who also logged the borings and prepared the samples for subsequent laboratory testing and reference. Boring elevations were obtained from a topographic plan prepared by Thaelien Engineering, Inc., dated June, 1981.

Soil Testing

In the field, earth materials were visually classified according to the Unified Soil Classification System by a careful examination of the samples and continuous observation of the boring returns. A description of this classification system is given at the front of Appendix A.

In the laboratory, samples taken from borings were tested to determine moisture content, dry density, maximum dry density, expansion potential, shear strength, consolidation characteristics, Resistance value, soluble sulfates, and corrosivity (resistivity and pH). The moisture density test results are shown on the Test Boring Logs and the results of other tests are given in Appendix B, on pages B-1 through B-5. Briefly, these tests were conducted as follows.

A compaction test was performed on a near surface sample in order to determine the maximum dry density and optimum moisture content of representative soils. This test was carried out in accordance with ASTM Test Method D 1557-70. The test results are shown on page B-1.

Expansion tests were performed on two samples of representative soils in accordance with the standard procedure for the Expansion Index Test (UBC Standard 20-2). In this testing procedure, the remolded sample is compacted with an energy input of 11,300 ft-lbs per cubic foot at 50% saturation. After remolding, the sample is confined under a pressure of 14.7 psf and allowed to soak for twenty-four hours. The resulting volume change due to increase in moisture content is recorded together with initial moisture content and dry density. The results of the expansion tests are presented on page B-1.

Shear characteristics of the foundation soils were determined in the laboratory by direct shear tests performed on two undisturbed samples. Samples were saturated and tested under several different normal loads in 2.5-inch I.C. circular shear box, using a controlled displacement rate of 0.01-inch per minute. Results of these tests are presented on pages B-1 and B-2.

MOORE & TABER CONSULTING ENGINEERS AND GEOLOGISTS

Settlement characteristics of five-representative samples were evaluated by means of laboratory consolidation tests. These samples were tested in a floating ring consolidometer using a dead weight lever system for load application. Test results are shown on the "Consolidation Test-Pressure Curves," pages B-3 through B-5.

A Resistance (R-value) test was performed on a typical subgrade sample. Testing was conducted in accordance with Test Method No. California 301-F. The results of this test are given on page B-1.

The concentration of soluble sulphates was determined for two representative samples of surficial soil in accordance with Test Method No. California 417. The results of this test are given on page B-1.

Corrosivity tests were performed on two samples to determine the minimum resistivity and pH of the soils. These tests were conducted in accordance with Test Method California 643C and the results are shown on page B-1.

July 18, 1981

Site Conditions and Earth Materials

At the time of our investigation, the subject property was occupied by several small businesses housed in quonset huts or Butler type buildings. The ground surface throughout the project area is fairly flat and has no discernible drainage pattern. Driveways and other open spaces between structures generally were covered with broken asphalt or other debris. Several piles of loose, dumped earth material and debris were scattered over the site. Overhead and subsurface utility lines are present on the property.

The earth materials encountered within the depth of exploration consisted of a variable depth of loose fill underlain by native alluvial sediments of Pleistocene age.

Generally, a mantle of loose fill approximately one to five feet in thickness covers the majority of the site. This fill is composed of fine silty sand and sandy and clayey silt with intermixed trash and debris. Deeper fill areas believed to be former oil sums were encountered in Boring 2, 3, and 8. These sump areas range up to approximately ten to fifteen feet in depth and contain debris laden fill along with bentonite, asphalt, and oil.

The native alluvial deposits underlying the fill consist of interbedded layers of semicompact to dense, fine to medium silty sand and soft to very stiff clayey and sandy silt.

Some water seepage was observed in the oil sum at Boring 8 at a depth of about six feet. This water is believed to be an extremely local effect confined to the oil sum area.

A more detailed description of the earth materials encountered is given on the Test Boring Logs.

CONCLUSIONS AND RECOMMENDATIONS

General

Footing foundations placed in firm native soil or approved compacted fill may be utilized for support of the proposed structures. A shallow, surficial layer of loose fill covers most of the project area. Moreover, oilumps or deeper pockets of fill are also present on the site. All loose fill should be removed and replaced as approved compacted fill.

Chemical analyses indicate that on-site soils may be severely corrosive to buried metal conduit.

Excavation Preparation

A variable depth layer of loose fill and isolated oilsumps are present within the project area. At the initial stage of grading it will be necessary to search out, remove and replace all loose material or debris. To increase the probability that all existing fill and oilsumps are located, a special probing procedure is advised. This procedure should consist of removing all fill to a depth of eighteen inches and proof-rolling the excavated surface with a single pass of heavy rubber-tired equipment. The compaction induced by the equipment should be sufficient to locate soft areas. All loose fill and oilsumps should be excavated under close observation of the soil technician and properly backfilled in the following manner.

After removal of the poor material, the top eight inches of the exposed surface should be compacted to at least 90% of maximum density at about optimum moisture. If approved by the soil engineer, the excavated material may then be replaced as compacted fill. All debris and deleterious material should be disposed off-site.

All fill should be placed in accordance with the recommendations presented in the subsequent section of this report entitled "Grading Requirements".

Footings Foundations

Footings placed at least 18 inches below the lowest adjacent grade in firm native soil or approved compacted fill may be designed for a maximum allowable bearing pressure of 2000 psf. This bearing value may be increased by one-third for short term seismic or wind loading.

Providing the above recommendations are followed, the calculated settlement under the maximum assumed column load of 80 kips is about 0.9-inch. Post-construction differential settlement is estimated to be about 0.25-inch.

Lateral Loads

Lateral forces may be resisted by friction between the supporting soils and the bottom of footings. An allowable coefficient of friction of 0.35 is considered applicable for on-site soils. The recommended lateral bearing value of undisturbed native soil or approved compacted fill is 150 psf/foot of depth. If coefficient of friction and lateral bearing are used in combination, the coefficient of friction should be reduced by 25%.

Concrete Slabs

Concrete slabs on grade should be supported on at least 12 inches of soil with a minimum relative compaction of 90%. The existing on-site soils are not expansive, and if expansive soils are not imported, reinforcement or special processing for expansive soils will not be necessary. If expansive soils are imported, recommendations for reinforcement and special processing can be presented at the time of grading.

Concrete Corrosion

Laboratory tests indicate only a slight concentration of soluble sulphate within the native soil. Consequently, no special cement need be utilized in concrete that comes in contact with on-site soil.

Metallic Corrosion

Laboratory tests show that the foundation soils exhibit a very low electrical resistivity. This condition may indicate a potentially severe corrosive environment for metal conduit. It is recommended that an engineer with expertise in corrosion be consulted regarding suitable types of conduits or any necessary protective measures.

Pavement Design

Pavement sections have been determined by the State of California Department of Transportation (Caltrans) method of flexible pavement design, using a traffic index of 4.0 for automobile parking and drives, and 5.0 for

areas subject to truck traffic. A Resistance value of 15 has been determined for the subgrade material. With these conditions, the following pavement sections are recommended.

Areas Subject to Automobile Traffic Only (T.I. = 4.0, R = 15)

Alternate 1	0.20'AC/0.55'AB
Alternate 2	0.45'AC Full Depth Section

Areas Subject to Truck Traffic (T.I. = 5.0, R = 15)

Alternate 1	0.25'AC/0.70'AB
Alternate 2	0.55'AC Full Depth Section

Asphalt concrete (AC) and aggregate base (AB) should conform to, and be placed in accordance with the latest revision of the Caltrans Standard Specifications. Prior to placing the pavement section, the subgrade soil should have a minimum relative compaction of 90% to a depth of 12 inches.

Drainage

Positive drainage of surface water away from the structures and to the parking and drive areas is very important. Water should not be allowed to pond at any location. Where slabs or pavement are not feasible adjacent to the buildings, the ground surface should be provided with a minimum gradient of about 6% to a distance of five feet away from the structures. Water should be transported off the site in approved drainage devices or unconstructed swales with a gradient of at least 1%. Swales or drainage paths through lawn or planting areas should be provided with a gradient of at least 2%. Where necessary, drainage paths could be shortened by use of area drains and collector pipes.

Planters adjacent to the structures should be avoided insofar as possible. Planting areas at grade should be provided with good positive drainage directed away from the building. Planters should not be depressed unless provisions for drainage, such as catch basins and pipe drains, are made.

Grading Requirements

These requirements should be furnished to the grading contractor.

The grading contractor is responsible for notifying the governmental agency, as required, and for notifying the soil engineer at the start of site clean-up, the start of grading operations, and any time that grading operations are resumed after an interruption. Each step of the operations described below must be approved in a specific area by the soil engineer and, where required, by the appropriate governmental agency or agencies before proceeding with subsequent work.

All site clean-up and grading will be subject to the approval of this office and must conform to the requirements of the City of Santa Fe Springs and the following recommendations.

If parties other than Moore & Taber are contracted to provide control during grading operations, they must be notified of their assumption of responsibility for the successful completion of the geotechnical phase of the project.

- (1) Prior to the start of grading, all vegetation, trash, surface obstructions, and debris resulting from demolition should be removed and disposed off-site. Any existing irrigation, drainage or utility lines or other abandoned subsurface structures should be removed, destroyed or abandoned in compliance with specifications of the appropriate building official and recommendations of this office.
- (2) Subsequent to clean-up operations, a reasonable search should be made for subsurface obstructions, oil sums and/or possible loose fill or detrimental soil types. This search should be conducted at the discretion and under the supervision of the soil engineer with the use of on-site equipment, as described in the section of the report entitled "Foundation Preparation".
- (3) The resulting clean natural ground surface should be scarified, brought to about optimum moisture content, and compacted to a minimum of 90% relative compaction for a depth of eight inches below the existing or stripped surface, unless otherwise noted. Reference is directed to the sections on "Concrete Slabs" and "Pavement Design" for additional grading requirements.
- (4) Fill should consist of approved earth material free of trash or deleterious materials. Vegetation or other deleterious material. All fill, except expansive soil placed within three feet of finished grade, **should be** spread in six to eight-inch lifts, brought to about optimum moisture, and compacted to at least 90% of maximum density as determined by ASTM 1557-70. All expansive soil placed within three feet of finished grade should be placed at well over optimum moisture content (about 140% of optimum) and compacted to at least 87%, but not more than 92% of maximum density.

- (5) All trench backfills, except for the bedding and six inches of cover, should be compacted to 90% of maximum density.

General Conditions

This report is based on the project as described and the geotechnical data obtained from the field tests performed at the locations indicated on the plan. The conclusions and recommendations do not reflect any non-linear variations which may occur between the field tests. Our firm should be notified of any pertinent change in the project or foundation plans. If foundation conditions are found to differ from those described herein, it may require a revaluation of the recommendations.

Our recommendations for this site are to a high degree dependent on proper fill placement and compaction. Consequently, our foundation recommendations are made contingent upon the opportunity for Moore & Taber to observe grading operations and foundation excavations for this phase of construction. If parties other than Moore & Taber are engaged to provide such services, they must be notified that they will be required to assume ultimate responsibility for the geotechnical phase of the project by concurring with the recommendations in this report or providing alternate recommendations.

This report has not been prepared for use by parties or projects other than those named or described above. It may not contain sufficient information for other parties or other purposes. It has been prepared in accordance with generally accepted geotechnical practices, and makes no other warranties, either expressed or implied, as to the professional advice or data included in it.

MOORE & TABER

Ted Primas *SPW*

Ted. M. Primas
Project Engineering Geologist
TMP/JJW:rb


Reviewed by J. J. Weaver
Registered Civil Engineer 32316

(6) Copies to Mr. Phil Campbell
Job No. 181-65 - August 26, 1981

APPENDIX A
FIELD EXPLORATION

UNIFIED SOIL CLASSIFICATION

PL	CH	CH	MH	OL	CL	ML	SC	SM	SP	SW	GC	GM	GP	GW
-75% organic soils	Silts and clays Liquid limit greater than 50			Sands and clays Liquid limit less than 50			Sands with fines >12% fines	Clean sands <5% fines	Gravels with fines >12% fines	Clean gravels <5% fines				
							Sands - more than 50% of coarse fraction is smaller than No. 4 sieve		Gravels - more than 50% of coarse fraction is larger than No. 4 sieve					
Fine grained soils (More than 50% is smaller than No. 200 sieve)							Coarse grained soils (More than 50% is larger than No. 200 sieve)							



LABORATORY CLASSIFICATION CRITERIA

GW and SW - $C_u = \frac{D_{50}}{D_{10}}$ greater than 4 for GW & 6 for SW; $C_s = \frac{(D_{50})^2}{D_9 \times D_{10}}$ between 1 & 3.

GP and SP - Clean gravel or sand not meeting requirements for GW and SW.

GM and SM - Atterberg limits below "A" line or P.L. less than 4.

GC and SC - Atterberg limits above "A" line with P.L. greater than 7.

Fines (silt or clay)	Fine sand	Medium sand	Coarse sand	Fine gravel	Coarse gravel	Cobbles	Pebbles
Sieve sizes	8	2	0	*	**	***	****

Classification of earth materials shown on this sheet is based on field inspection and should not be construed to imply laboratory analysis unless so stated.

MATERIAL SYMBOLS

	Gravel		Peat or organic matter
	Sand		Fill material
	Silt		Shale
	Clay		Sandstone
	Silty clay or loamy sand		Limestone
	Sandy silt or silty sand		Metamorphic rock
	Clayey silt or clayey sand		Igneous rock

CONSISTENCY CLASSIFICATION

FOR SOILS

According to the Standard Penetration Test

Nº of blows	Granular	Cohesive
0-5	Very loose	Very soft
6-10	Loose	Soft
11-20	Semicompact	Stiff
21-35	Compact	Very stiff
36-70	Dense	Hard
>70	Very dense	Very hard

LEGEND OF BORING

Bulk sample	Conformable material change
Drive sample	Approximate material change
1 GWS	

LEGEND OF PENETRATION TEST

15	24	30	35	41	27	39	GWS	5

Blows per foot
(Using 140 lb hammer with 30" drop; 350 ft/lb blow)

0 20 40
B.P.F /

Graphic representation of driving rate.

TEST BORING LOG

TYPE	16" Bucket						ELEVATION 156.5	BORING		
	STRIKE	DIP	RELATIVE CONTACT	DRY DENSITY (LB/SCU FT)	MOISTURE (%)	B.G.S./FOOT 500' F.L.				
SAMPLE #	DEPTH IN FEET	SAMPLE SIZE (INCHES)	MATERIAL NAME	UNIFORM SOIL CLASS	NOTES:					
									Broken asphalt and base rock	
104.2	12.0	2	2.5	1	2	5	NATURAL: Dark red-brown SANDY SILT ... color change to red-brown - minute voids ... lighter red-brown color at 4' ... increasing SAND ... decreasing SAND ... color change at 10' to light greenish brown - sample has minute voids ... cemented modules of SANDY SILT ... sample has minute voids and material is cemented	ML		
103.3	14.9	1	2.5	3		10				
91.3	17.9	4	2.5	4		15				
101.2	21.7	5	2.5	5		20				

NOTES:

- 1) End of hole 16'.
- 2) No caving.
- 3) No groundwater encountered.
- 4) Backfilled 7-23-81.

TEST BORING LOG

TYPE	16" Bucket						ELEVATION 157.5	BORING	
	STRIKE	DIP	RELATIVE CONTACT	DRY DENSITY (LB/SCU FT)	MOISTURE (%)	B.G.S./FOOT 500' F.L.			
SAMPLE #	DEPTH IN FEET	SAMPLE SIZE (INCHES)	MATERIAL NAME	UNIFORM SOIL CLASS	NOTES:				
									FILL: 6" broken asphalt and green SILTY SAND, black fine-medium SILTY SAND with glass and nails. ... slight oil smell at 3' ... wire at 4.5'
101.2	12.0	2	2.5	1		5	SM		
110.7	13.0	3	2.5	2		10	ML		gray SANDY SILT with oil smell - SUNP ... mixed with drilling mud
109.1	13.1	2	2.5	3		15	ML		... roots at 14'
92.1	14.1	2	2.5	4		20	CL		NATURAL: mottled gray-green CLAYEY SILT

NOTES:

- 1) End of boring 16'.
- 2) No caving.
- 3) No groundwater encountered.

THESE BORING LOG SUMMARIES APPLY ONLY AT THE TIME AND LOCATION INDICATED. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND TIMES.

LOGGED BY	DATE
W.M. Moore	7-23-81

TEST BORING LOG

TYPE	16" Bucket							ELEVATION 158.0	BORING
		DEPT	DEPT	DEPT	DEPT	DEPT	DEPT		
101.0	22.0	P	2.5 Bag	1 2	5			SN	Broken asphalt and base with yellow-brown SILTY SAND.
97.9	28.5	P	2.5	3				CSC	FILL: gray CLAYEY SAND with GRAVEL to 2".
99.0	26.3	P	2.5	4	10			SH.	white bentonite with GRAVEL to 2.5"
									mottled blue-gray CLAYEY SILT with slight oil smell
									mottled blue-gray CLAYEY SILT and SAND with strong oil smell - SILT
									NOTES:
									1) End of boring 11'. 2) Caved back to 9'. 3) No groundwater encountered. 4) Backfilled 7-23-81.

TEST BORING LOG

TYPE	16" Bucket							ELEVATION 158.0	BORING	
		DEPT	DEPT	DEPT	DEPT	DEPT	DEPT			
117.4	11.0	S	0.5 Bag	1 2	5			ML	3" broken asphalt NATURAL: red-brown CLAYEY SILT with minute voids.	
115.7	11.4	S	0.5 Bag	2 3				ML	red-brown SANDY SILT with minute voids ... color changed to light red-brown	
115.5	11.7	S	0.5	4	5			ML	red-brown cemented CLAYEY SILT	
									gray-green SANDY SILT with minute root voids	
									NOTES:	
									1) End of boring 16'. 2) No caving. 3) No groundwater encountered. 4) Backfilled 7-24-81.	
STRIKE S/F	RELATIV COMPAC TION	DRY DENSIT (LBS/CU FT)	MOISTURE (%)	BLOCS/FOOT (5000 LB/50)	SAMPLE SIZE (INCHES)	SAMPLE NO.	DEPTH IN FEET	MATERIAL SYMBOL	UNIFIED SOIL CLASS.	THESE BORING LOG SUMMARIES APPLY ONLY AT THE TIME AND LOCATION INDICATED. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND TIMES.
										LOGGED BY TIP : DATE 7-24-81

TEST BORING LOG

TYPE	16" BOREHOLE						ELEVATION 153.1	BORING
	SS.1	14.7	2	Sag	1		ML	FILL: brown SANDY SILT with trace of CLAY and wood fragments
	101.6	9.5	2	2.5	3	5	SM	NATURAL: light brown fine SILTY SAND
	103.1	12.0	2	2.5	4		ML	dark red-brown CLAYEY SILT ... color change to red-brown at 9' with minute voids
	112.2	15.6	4	2.5	5	10	ML	
	101.1	19.0	5	2.5	6	13	SM	light yellow-brown micaceous SANDY SILT
						20		light yellow-brown micaceous fine SILTY SAND with voids
								1) End of boring 16'. 2) No caving. 3) No groundwater encountered. 4) Backfilled 7-23-81.

TEST BORING LOG

TYPE	16" BOREHOLE						ELEVATION 157.3	BORING	
	SS.1	13.1	2	2.5	1		ML	FILL: yellow-brown SANDY SILT with GRAVEL and A.C. ... wire at 2.5'	
	101.6	13.4	2	2.5	2	8	ML	NATURAL: mottled yellow-brown SANDY SILT	
	118.1	18.3	4	2.5	3	10	ML	red-brown CLAYEY SILT ... minute voids	
	101.1	19.0	4	2.5	4	13	SM	light red-brown SANDY SILT	
						20		yellow-brown fine-medium SILTY SAND	
								NOTES: 1) End of boring 16'. 2) No caving. 3) No groundwater encountered. 4) Backfilled 7-23-81	
STRIKE DIP	RELATIVE COMPACTNESS	DRY DENSITY (LBS/CF)	MOISTURE (%)	SOIL TESTS 1500 C.P.	SAMPLE SIZE (INCHES)	SAMPLE #	DEPTH IN FEET	MATERIAL SYMBOL UNIFIED SOIL CLASS	THESE BORING LOG SUMMARIES APPLY ONLY AT THE TIME AND LOCATION INDICATED. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND TIMES.
									LOGGED BY <u>T.P.</u> DATE 7-23-81

TEST BORING LOG

TYPE	16" Bucket						ELEVATION 157.9	BORING
	STRIKE	DIP	RELATIVE COMPAC-	DRY DENSITY	SAMPLE SIZE	DEPTH IN FEET		
		COMPAC-	(LBS/CF)	(INCHES)		MATERIAL SYMBOL	UNIFIED SOIL CLASS	
								FILL: mottled black SILTY SAND with trash debris and oil smell
98.8	17.0	3	2.5	1		5	SM	mottled brown SANDY SILT
79.7	32.1	3	2.5	2		10	ML	NATURAL: yellow-green fine SILTY SAND with oil smell
226.1	5.8	3	2.5	3		15	SM	dark red-brown CLAYEY SILT with organic debris and some voids
109.8	15.9	P	2.5	4		20	ML	yellow-brown fine SILTY SAND
108.8	17.4		2.5	5				NOTES: 1) End of boring 16'. 2) No caving. 3) No groundwater encountered. 4) Backfilled 7-23-81.

TEST BORING LOG

TYPE	16" Bucket						ELEVATION 158.6	BORING 3
	STRIKE	DIP	RELATIVE COMPAC-	DRY DENSITY	SAMPLE SIZE	DEPTH IN FEET		
		COMPAC-	(LBS/CF)	(INCHES)		MATERIAL SYMBOL	UNIFIED SOIL CLASS	
								concrete and GRAVEL
34.5	19.2	3	2.5	1		5	ML	FILL: mottled black and gray CLAYEY with some trash (nails, wood) and oil smell
41.8	19.7	3	2.5	2		10	ML	gray-green CLAYEY SILT with oil smell and getting very wet (oil sump)
100.7	17.1	3	2.5	3		15	SL	mottled blue-gray medium CLAYEY SAND with oil smell (oil sump)
								NATURAL: gray-black CLAYEY SILT with voids
								NOTES: 1) End of boring 16'. 2) No caving. 3) Groundwater encountered. 4) Backfilled 7-24-81. 5) Groundwater encountered at 6' 7-24-81.
STRIKE	DIP	RELATIVE COMPAC-	DRY DENSITY	SAMPLE SIZE	DEPTH IN FEET	MATERIAL SYMBOL	UNIFIED SOIL CLASS	THESE BORING LOG SUMMARIES APPLY ONLY AT THE TIME AND LOCATION INDICATED. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND TIMES.
		COMPAC-	(LBS/CF)	(INCHES)				LOGGED BY T.P. DATE 7-23-81

MOORE TABER CONSULTING ENGINEERS AND GEOLOGISTS

TEST BORING LOG

TYPE	10' Bucket				ELEVATION 135.0	BORING
113.3	13.6	2	2.5	1	ML	FILL: mottled gray-green CLAYEY SILT ... color change to mottled yellow-brown
115.7	13.9	3	2.5	2	5 ML	NATURAL: dark red-brown CLAYEY SILT with voids ... color change to red-brown - some SAND
116.2	14.9	4	2.5	3	10	
			Bag	4	ML	gray-green CLAYEY SILT with trace of SAND and voids
97.7	22.2	14	2.5	5	15	
			Bag	6	SM	yellow-green fine SILTY SAND
108.9	8.6	10	2.5	7	20	
						NOTES: 1) End of boring 16'. 2) No caving. 3) No groundwater encountered. 4) Backfilled 7-24-81

TEST BORING LOG

TYPE	BUCKET			ELEVATION	157.5	BORING	10
106.0	10	1	2.5	1	ML	FILL: brown SANDY SILT with weeds and grass	
114.0	11	2	2.5	5	ML	NATURAL: mottled red-brown and gray CLAYEY SILT with roots and voids and organic debris	
115.0	12	3	2.5	10	SM	gray-green fine SILTY SAND with roots	
115.0	13	4	2.5	10	ML	brown CLAYEY SILT with voids ... sample has minute voids ... some fine SAND ... color change to mottled gray-brown at 13.5'	
114.0	14	4	2.5	13	SM	yellow-brown fine micaceous SILTY SAND	
				20		NOTES: 1) End of boring 16'. 2) No caving. 3) No groundwater encountered. 4) Backfilled 7-24-81.	V

THESE BORING LOG SUMMARIES APPLY ONLY AT THE TIME
AND LOCATION INDICATED. SUBSURFACE CONDITIONS
MAY DIFFER AT OTHER LOCATIONS AND TIMES.

LOGGED BY TIP | DATE 7-24-81


TEST BORING LOG


TYPE	16" DIA. BOREHOLE						ELEVATION	BORING
	110.6	10.4	2	2.5	1	SM		
	108.5	14.2	1	2.5	2	NATURAL	FILL: orange-brown SILTY SAND with roots and grass	
					5	NATURAL	NATURAL: brown CLAYEY SILT with voids ... color change to red-brown at 4'	
	94.0	24.4	10	2.5	3	NATURAL	gray-green SANDY SILT	
	97.0	26.1	6	2.5	4	NATURAL	gray fine SILTY SAND	
					15	SM	NOTES:	
					20		1) End of boring 16'.	
							2) No caving.	
							3) No groundwater encountered.	
							4) Backfilled 7-24-81.	

TEST BORING LOG

TYPE	16" DIA. BOREHOLE						ELEVATION	BORING
	110.6	10.4	2	2.5	1	SM		
	108.5	14.2	1	2.5	2	NATURAL	FILL: brown CLAYEY SILT with trash debris	
					5	NATURAL	NATURAL: brown CLAYEY SILT with voids and roots	
	94.0	24.4	10	2.5	3	NATURAL	gray-green SANDY SILT	
	97.0	26.1	6	2.5	4	NATURAL	gray fine SILTY SAND	
					15	SM	NOTES:	
					20		1) End of boring 2'.	
							2) No caving.	
							3) No groundwater encountered.	
							4) Backfilled 7-24-81.	


STRIKE	DIP	RELATIVE COMPACTION	DRY DENSITY (LB/SQ.FT.)	MOISTURE (%)	BLOKS/FOOT 1500 ft/lbs	SAMPLE SIZE (INCHES)	SAMPLE NO.	DEPTH IN FEET	MATERIAL SYMBOL	UNIFIED SOIL CLASS
										THESE BORING LOG SUMMARIES APPLY ONLY AT THE TIME AND LOCATION INDICATED. SUBSURFACE CONDITIONS MAY DIFFER AT OTHER LOCATIONS AND TIMES.
										LOGGED BY TWP DATE 7-24-81

 SCALE 1"=50'



LOT N°1 PARCEL MAP N°14608 SANTA FE SPRINGS, CA.			
LOCATION OF BORINGS			
MOORE & TABER - Engineers - Geologists			
DRAFT. A.L.S.	APPROV. <i>OTW</i>	DATE 8-26-81	JOB N° 181-66

LOS NIETOS ROAD



GREENLEAF

AV


APPENDIX B
LABORATORY TESTING & RESULTS

MOORE & TABER -Engineers-Geologists


SOIL TEST RESULTS

BORING NO. / SAMPLE NO.	1/2	3/2	5/1	7/1	7/2
DESCRIPTION	Brown CLAYEY SILT	Gray CLAYEY SILT	Gray-Brown CLAYEY SILT	Green SANDY SILT	Brown SANDY SILT
UNIFIED SOIL CLASSIFICATION	HL	ML	ML	ML	ML
DIRECT SHEAR TEST (lb./sq.ft.)				Undisturbed	
Initial Moisture Content %				17.0 17.0 17.0	
Test Moisture Content %				Saturated	
Normal Stress (lbs./sq.ft.)				990 1980 2970	
Peak Shear Stress (lbs./sq.ft.)				1450 2170 2300	
Ultimate Shear Stress (lbs./sq.ft.)				860 1450 2020	
Angle of Internal Friction (degrees)				30	
Cohesion (lbs./sq.ft.)				300	
EXPANSION TEST	UBC 29-2				UPC 29-2
Initial Dry Density (lbs./sq.ft.)	113.5				109.5
Initial Moisture %	9.0				10.0
Final Moisture %	14.8				17.2
Pressure (lbs./sq.ft.)	144				144
Expansion Index Swell %	8 0.8				5 0.5
INFLATION TEST (type)			ASTM D1557-70		
Maximum Dry Density (lbs./sq.ft.)			116.0		
Moisture %			13.8		
WATER VAPOR PERMEATES			Calif. 417A		
Concentration %			6.0959		
(ohm-cm)			Calif. 643		
Conductivity			7.5		
Calif. 301-F			555		
		15			


CONSOLIDATION TEST - PRESSURE CURVES




CONSOLIDATION TEST - PRESSURE CURVES



CONSOLIDATION TEST - PRESSURE CURVES



CONSOLIDATION TEST - PRESSURE CURVES




CONSOLIDATION TEST - PRESSURE CURVES

Box / Sample No. 775

Elev. - Depth 10'

Date 8-26-81




CONSOLIDATION TEST - PRESSURE CURVES

Box / Sample No.

Elev. - Depth

Date



AMMOND SOILS ENGINEERS

PRELIMINARY SOILS INVESTIGATION • FOUNDATION STUDIES

FILL CONTROL

Job No. F75-115
October 22, 1975

PHONE 434-4801

199 N. STATE COLLEGE BLVD. • ORANGE, CALIFORNIA

FINAL REPORT OF COMPAKTED FILL

Compacted Building Pad for Proposed Industrial Building, located at 12707 Los Nietos Road, City of Santa Fe Springs, California.

Developer: Coastal Developers Co.

Introduction

This report presents the results of field and laboratory tests and field supervision provided for during the excavation of fill materials, the processing and compaction of the exposed natural ground and the adequate placement and compaction of structural fill soils to construct the subject building pad. These soils engineering services were provided for by agreement with Steve McMillian representing Coastal Developers Company.

Grading Procedure

Grading operations were conducted by the Coastal Developers Company during the months of September and October, 1975. Prior to the grading of the site the ground surface was stripped of existing vegetation and debris. After the building area had been properly cleaned, the excavation of existing fill materials was conducted. All fill materials were completely excavated to a depth of 8.0 feet in the building area and at least 8 feet beyond the limits of the proposed building. After the fill soils had been excavated the underlying natural ground was processed for 12 inches and was compacted to at least 90% relative compaction. The excavated soils were then used for structural fill purposes and the soils were clean, stable earth materials free of deleterious substances. These soils were placed in thin lifts of 6 to 8 inches at near optimum moisture and were compacted by sheepsfoot equipment to at least 90% relative compaction. The rest of the building pad area was processed for a depth of 12 inches and compacted to 90% relative compaction. The maximum depth of the compacted fill soils in the building pad area was obtained by estimates made in the field and was on the order of 8.0 feet.

Testing

Maximum density determinations were made on the typical structural fill soils in accordance with the Standard Test Method

MR. Olliso-

AMMOND SOILS ENGINEERING

PRELIMINARY SOILS INVESTIGATION • FOUNDATION STUDIES

FILL CONTROL.

Job No. F75-115
October 22, 1975

-2-

PHONE 834-4801

199 N. STATE COLLEGE BLVD. • ORANGE, CALIFORNIA

A.S.T.M. D1557-70T with 25 blows in each of 5 layers with a 10 lb. hammer falling 18 inches in a mold of 1/30 cu.ft. volume.

Soil A Medium brown sandy silt with clay binder; Maximum density 113.1 lbs./cu.ft. at 14.7% optimum moisture.

Soil B Medium brown sandy silt; Maximum density 118.3 lbs./cu.ft. at 12.2% optimum moisture.

Soil C Medium brown silty fine sand; Maximum density 115.7 lbs./cu.ft. at 12.7% optimum moisture.

The results of a textural and visual analysis of the typical foundation soils and expansion tests performed on remolded samples of soils compacted to over 90% and measured from oven dry to saturation after a period of several days and in complete accordance with the procedures as outlined by the "International Conference of Building Officials" are as follows:

Expansion Tests

<u>Soil Type</u>	<u>Confining Load</u>	<u>% Expansion</u>
A	650 p.s.f.	0.4
A	60 p.s.f.	3.0
B	650 p.s.f.	0.3
B	60 p.s.f.	1.5
C	650 p.s.f.	0.6
C	60 p.s.f.	2.5

The results of the expansion tests indicate that the typical foundation soils are slightly-expansive with respect to detrimental seasonal volume change.

The results of relative compaction tests taken daily during the grading operations are as follows:

<u>Test No.</u>	<u>Soil Type</u>	<u>Field Moisture (%)</u>	<u>Dry Density (lbs./cu.ft.)</u>	<u>Relative Compt. %</u>
S-1	B	15.0	114.2	97
S-2	B	17.2	110.6	93
S-3	B	12.4	113.9	96

HAMMOND SOILS ENGINEERING

PRELIMINARY SOILS INVESTIGATION - FOUNDATION STUDIES

FILL CONTROL

Job No. F75-115
October 22, 1975

-3-

PHONE 824-4801

199 N. STATE COLLEGE BLVD. • ORANGE, CALIFORNIA

<u>Soil Test No.</u>	<u>Soil Type</u>	<u>Field Moisture (%)</u>	<u>Dry Density (lbs./cu.ft.)</u>	<u>Relative Compt. %</u>
S-4	B	16.8	114.0	96
S-5	A	21.0	102.4	91
S-6	A	17.3	101.7	90
S-7	B	17.9	106.7	90
S-8	B	14.8	111.3	94
S-9	B	15.3	113.0	95
S-10	B	18.0	109.3	92
S-11	B	18.1	110.7	94
S-12	C	14.1	104.9	91
S-13	B	12.8	116.9	98
S-14	B	16.0	110.1	93
S-15	A	13.5	109.6	97
S-16	A	13.5	103.6	92
S-17	A	17.7	106.4	94
S-18	A	8.4	106.1	94
S-19	B	17.5	110.9	94
S-20	B	17.3	112.6	95
S-21	A	20.0	102.5	91
S-22	B	16.0	111.0	94
S-23	B	15.2	108.0	91
S-24	B	16.3	113.1	96
S-25	B	18.7	107.3	91
S-26	B	17.4	109.4	92
S-27	B	15.7	113.6	96
S-28	B	17.1	110.2	93
S-29	B	8.4	105.9	90
S-30	C	14.4	104.8	91
S-31	C	14.7	109.7	93
S-32	C	11.8	101.4	90
S-33	B	13.4	109.4	93
S-34	C	7.4	104.8	91
S-35	B	16.0	108.7	92

Conclusions and Recommendations

All of the cleanup operations, the excavations of fill materials, compaction of the natural ground and the final placement and compaction of structural fill soils were conducted in accordance with provisions of Chapter 70 of the Uniform Building Code and were also in compliance with all of our specifications and testing

HAMMOND SOILS ENGINEERING

PRELIMINARY SOILS INVESTIGATION • FOUNDATION STUDIES

FILL CONTROL

PHONE 833-8810

108 N. STATE COLLEGE BLVD. • ORANGE, CALIFORNIA

Job No. F75-115
October 22, 1975

-4-

procedures. Allowable soil bearing pressures are now applicable for various sizes and types of footings as outlined in our Fill Investigation and Preliminary Soils Study, dated August 4, 1975, Job No. F75-99.

Based on the results of expansion tests and the results of the inspection and tests made during the grading and compaction operations, it is concluded that all of the pertinent foundation soils in proximity to the footings and slabs are non-expansive with respect to detrimental seasonal volume change.


It is suggested that a moisture barrier such as a polyethylene membrane be used beneath floor slabs where office areas might be involved and this will minimize the possibility of excessive moisture coming through the floors. In addition to this, fine grading, paving and landscaping should provide positive and permanent drainage away from all foundation areas and be directed towards the streets or approved drainage devices.

Respectfully submitted,

HAMMOND SOILS ENGINEERING



By Ross Hammond



Reviewed By Ronald W. Martin
R.C.E. 14455



RH:plk
4-Coastal Developers

12707 Los Nietos Road, Santa Fe Springs
Coastal Developers Company

AAZ

Job No. F75-115

10-22-75




SCALE 1" = 50'

LOS NIETOS ROAD

LEGEND

• APPROXIMATE LOCATIONS OF RELATIVE COMPACTION TESTS



APPROXIMATE LIMITS OF COMPACTED SOILS IN BUILDING PAD AREA

HAMMOND SOILS ENGINEERING

PRELIMINARY SOILS INVESTIGATION • FOUNDATION STUDY

FILL CONTROL

PHONE 633-8610

199 N. STATE COLLEGE BLVD. • ORANGE, CALIFORNIA

F I L L I N V E S T I G A T I O N

A N D

P R E L I M I N A R Y S O I L S S T U D Y

Proposed Industrial Building lo-
cated at 12707 East Los Nietos
Road, Santa Fe Springs, Calif.

Developer: Coastal Developers Co.
1019 Mammoth Way
Placentia, CA

Job No. F75-99

August 4, 1975

AMMOND SOILS ENGINEERING

PRELIMINARY SOILS INVESTIGATION • FOUNDATION STUDIES

Job No. F75-99

August 4, 1975

FILL CONTROL

PHONE 855-5610

199 N. STATE COLLEGE BLVD. • ORANGE, CALIFORNIA

FILL INVESTIGATION
AND PRELIMINARY SOILS STUDY

Proposed Industrial Building located at 12707 East Los Nietos Road, Santa Fe Springs, Calif.

Developer: Coastal Developers Co.

Introduction

This Fill Investigation and Preliminary Soils Study presents the results of field work and laboratory testing in accordance with the City of Santa Fe Springs Department requirements for the development of the proposed industrial building. The property is rectangular shape with a frontage along Santa Fe Springs of 176 feet and a depth or length of 290 feet. The proposed industrial building will be located along the east side of the site with driveway and parking facilities planned over the west side of the property. The land is relatively flat and appears to have been used for a storage area. A small metal building is located at the south end of the site along Los Nietos Road.

Should be
deeper
X

Field Investigation

A total of four backhoe excavations were made to depths ranging from 7 to 11 feet in the proposed building area to properly assess the existing soil conditions. The depth and frequency of these borings combined with a correlation of all of the soil and a study of the surrounding soil conditions provided a comprehensive surface and subsurface soils analysis with respect to the type of development intended.

The backhoe excavations uncovered fill materials which are located over approximately two-thirds of the proposed building pad area. These soils are described as mottled sandy silt and clay with some debris and deleterious material noted. Some oil contaminated soils were also noted. Our excavations indicate approximately 7.5 feet of fill at the extreme north end of the proposed building area with 8.5 feet of fill noted in the center of the building area. Excavations made at the south-end of the proposed building indicate a shallow surface fill of approximately 1.5 feet. During the grading operations it will be necessary to completely excavate all of the fill soils from the building area. After the fill material has been excavated



COMMOND SOILS ENGINEERING

PRELIMINARY SOILS INVESTIGATION • FOUNDATION STUDIES

FILL CONTROL

Job No. F75-99
August 4, 1975
-2-

PHONE 633-5610

199 N. STATE COLLEGE BLVD., ORANGE, CALIFORNIA

and all undesirable debris removed from the soil, then the excavated fill material should be mixed with clean soils and may be used for backfill and recompaction purposes.

The typical native soils encountered below the fill soils were fairly uniform in composition and classified as clayey fine sandy silt and fine sandy silts with clay binder. Moisture content was generally in the vicinity of optimum varying from a low of 11.2% to a high of 20.1%, however, no ground water surface was encountered to a depth of ten feet and should be considerably below this depth so that it will have no affect whatsoever on either the underground utilities or the proposed foundations. With proper cleaning and removal of the deleterious fill soils and the proper processing and compaction of the native soils, satisfactory stable foundation soil conditions can be expected for the proposed structural fills and resulting building pad.

Laboratory Testing

The results of laboratory tests performed on the typical foundation soils are as follows:

Soil Type A

Classification: Medium brown sandy silt w/ clay binder
 Maximum density: 113.1 lbs./cu.ft.
 Optimum moisture: 14.7%

Expansion tests were performed on the typical near surface soils, these samples were remolded to over 90% and measured from air dry to saturation after a period of at least 24 hours and until no further expansion was recorded to .001 inches.

Expansion Tests

<u>Soil Type</u>	<u>Confining Load</u>	<u>E.I.</u>	<u>% Expansion</u>
A	650 p.s.f.		0.3
A	144 p.s.f.	22	2.2
A	60 p.s.f.		3.0

Based on the results of the tests and an analysis of the boring logs, the soils indicate slightly expansive characteristics. During and at the completion of the grading operations, a careful check and control on the soils will be conducted and further expansion tests will be conducted at that time.

Direct shear tests were performed on saturated remolded samples of the typical foundation soils and are shown on the following table:

HAMMOND SOILS ENGINEERING

PRELIMINARY SOILS INVESTIGATION - FOUNDATION STUDY

FILL CONTROL

Job No. F75-99

August 4, 1975

-3-

PHONE 633-5610

199 N. STATE COLLEGE BLVD. • ORANGE, CALIFORNIA

Boring Sample No.	Water Content Natural (%)	Water Content Test (%)	Normal Stress (t.s.f.)	Peak Shear Stress Strain (t.s.f.)(ins.)	Ultimate Shear Stress (t.s.f.)	Ultimate Shear Strain (t.s.f.)(ins.)
A-1	18.9	21.2	0.5	.38 .100	.35	.250
A-2	19.2	21.8	1.0	.67 .110	.63	.250
A-3	18.5	21.0	1.5	.97 .150	.91	.250

The above tests determined an angle of internal friction of 29° with 100 p.s.f. available cohesion. Applying the Terzaghi Bearing Capacity Equation and using factors comparable to the existing soil conditions we have:

$$\begin{aligned}
 q &= C N_c + w D_f N_q + w B N_w \\
 &= 100(22) + 100(1.0)16 + 100(0.5)14 \\
 &= 2200 + 1600 + 700 \\
 &= 4500 \text{ p.s.f. (ultimate)}
 \end{aligned}$$

q_a = 1500 p.s.f. (allowable for square or continuous footings not less than 12 inches wide and embedded at least 12 inches below approved finished grade)

q_s = 1750 p.s.f. (allowable for square or continuous footings not less than 12 ins. wide and embedded at least 18 ins. below approved finished grade)

q_z = 2000 p.s.f. (allowable for square or continuous footings not less than 24 ins. wide and embedded at least 18 ins. below approved finished grade)

For large isolated square footings with a minimum width of 3.0' and a minimum depth of 18 inches, a bearing value of 2400 p.s.f. may be used.

Note: The above values may be increased by one-third for wind and seismic loads. A coefficient of friction of 0.4 between the bottom of the footings and adjacent soils may be used when considering lateral forces.

The results of moisture tests, density tests and relative compaction tests procured adjacent to the borings and from them are indicated on the Log of Test Borings drawings at their proper depths.

HAMMOND SOILS ENGINEERING

PRELIMINARY SOILS INVESTIGATION • FOUNDATION STUDIES

FILL CONTROL

Job No. F75-99
August 4, 1975

-4-

PHONE 633-8610

199 N. STATE COLLEGE BLVD. • ORANGE, CALIFORNIA

Grading and Foundation Recommendations

The cleanup operations will include the complete removal of all fill materials from the building pad area and extending beyond the footing areas for the depth of the fill materials. The excavated fill soils should be cleaned of any wood, debris or other deleterious materials and should then be mixed with clean soils to be used in the backfill and compaction of the excavation.

After the fill materials have been excavated to natural ground, the exposed native soils to a depth of approximately 12 inches should be processed, watered and mixed to approach optimum moisture and then thoroughly compacted, preferably by sheep-foot rolling to a minimum of 90% relative compaction. All structural fill soils must be free of deleterious substances and spread in lifts of 6 to 8 inches, watered to near optimum requirements or allowed to dry if necessary and compacted to a minimum of 90% relative compaction as determined by the A.S.T.M. D1557-70T (25 blows, 3 layers, 10 lb. hammer falling 18 inches in a mold of 1/30 cu.ft. volume).

Provided the above recommendations are followed, the soils constituting the building areas of the subject site are considered adequate for design loads of 1500 p.s.f. to 2400 p.s.f. as outlined in this report. As the typical soils are slightly expansive, no horizontal reinforcement of the foundations is considered necessary, however, additional expansion tests will be made during and at the completion of grading operations when final recommendations will be made. It is recommended that all the soils in the foundation areas be kept in a moist condition during the grading and they should again be sprayed with a hose so that they are moist prior to the time the footings and slabs are poured. Utilizing trenches that traverse the slab area should be properly backfilled and compacted by handtamping or wheelrolling with native soils or clean sand can be used which is flooded in place. Fine grading, paving and landscaping should provide positive drainage away from all foundation areas and be directed towards the streets or approved drainage devices.

Respectfully submitted,

HAMMOND SOILS ENGINEERING


By Ross Hammond

RH:plk
4-Coastal Developers Co.


Reviewed By Ronald W. Martin
R.C.E. 14456

TEST BORING LOG

HAMMOND SOILS ENGINEERING

Job No: F75-99

Type

BORING NO: 1,2

Soil description

Depth in feet						Soil description
	Dry density (lbs./cu.ft.)	Holsture (%)	Stand. Penet. (blows/ft)	Sample size (inches)	Sample No.	
0						BORING 1
5	102.0	155	1			Dry hard, mottled sandy silt w/ clay and some debris
10	13.9		2			Slightly comp. mottled moist, fine sandy silt w/ clay binder, slightly firm.
15						Firm red brown slightly sandy silt w/ clay binder
20						Firm to hard moist red brn clayey sli sandy silt
						BORING 2
0	98.9	20.1	1			Hard damp red brn silty fine sand (fill) w/ very little crushed brick
5						Layers of fill & dark gray brn oily sand (moist)
10			2			Firm red brn sli sandy silt with clay binder
15						
20						

TEST BORING LOG

HAMMOND SOILS ENGINEERING

Job No: F75-99

Type

BORING NO: 3,4
Soil description

Depth in feet					Soil description
	Dry density (lbs./cu.ft.)	Moisture (%)	Stand. Penet. (blows/ft)	Sample size (inches)	
0					BORING 3
5	108.0	15.1		1	Loose dry lt brn sli sandy silt
10					
15					
20					
25					
30					
35					
40					
45					
50					
55					
60					
65					
70					
75					
80					
85					
90					
95					
100					
105					
110					
115					
120					
125					
130					
135					
140					
145					
150					
155					
160					
165					
170					
175					
180					
185					
190					
195					
200					
205					
210					
215					
220					
225					
230					
235					
240					
245					
250					
255					
260					
265					
270					
275					
280					
285					
290					
295					
300					
305					
310					
315					
320					
325					
330					
335					
340					
345					
350					
355					
360					
365					
370					
375					
380					
385					
390					
395					
400					
405					
410					
415					
420					
425					
430					
435					
440					
445					
450					
455					
460					
465					
470					
475					
480					
485					
490					
495					
500					
505					
510					
515					
520					
525					
530					
535					
540					
545					
550					
555					
560					
565					
570					
575					
580					
585					
590					
595					
600					
605					
610					
615					
620					
625					
630					
635					
640					
645					
650					
655					
660					
665					
670					
675					
680					
685					
690					
695					
700					
705					
710					
715					
720					
725					
730					
735					
740					
745					
750					
755					
760					
765					
770					
775					
780					
785					
790					
795					
800					
805					
810					
815					
820					
825					
830					
835					
840					
845					
850					
855					
860					
865					
870					
875					
880					
885					
890					
895					
900					
905					
910					
915					
920					
925					
930					
935					
940					
945					
950					
955					
960					
965					
970					
975					
980					
985					
990					
995					
1000					
1005					
1010					
1015					
1020					
1025					
1030					
1035					
1040					
1045					
1050					
1055					
1060					
1065					
1070					
1075					
1080					
1085					
1090					
1095					
1100					
1105					
1110					
1115					
1120					
1125					
1130					
1135					
1140					
1145					
1150					
1155					
1160					
1165					
1170					
1175					
1180					
1185					
1190					
1195					
1200					
1205					
1210					
1215					
1220					
1225					
1230					
1235					
1240					
1245					
1250					
1255					
1260					
1265					
1270					
1275					
1280					
1285					
1290					
1295					
1300					
1305					
1310					
1315					
1320					
1325					
1330					
1335					
1340					
1345					
1350					
1355					
1360					
1365					
1370					
1375					
1380					
1385					
1390					
1395					
1400					
1405					
1410					
1415					
1420					
1425					
1430					
1435					
1440					
1445					
1450					
1455					
1460					
1465					
1470					
1475					
1480					
1485					
1490					
1495					
1500					
1505					
1510					
1515					
1520					
1525					
1530					
1535					
1540					
1545					
1550					
1555					
1560					
1565					
1570					
1575					
1580					
1585					
1590					
1595					
1600					
1605					
1610					
1615					
1620					
1625					
1630					
1635					


TEST BORING LOG

Job No: F75-99

HAMMOND SOILS ENGINEERING

Type

BORING NO: E-1, E-2
1 description





Coastal Developers Co.

AAZ

F7 99

8-4-75

HAWKINS SEALS ENGINEERING INC.
100 NO. STATELINE RD. BLVD.
CRAVEN, NC 28633
660-5010



SCALE 1:40'

L 5/1/75

Loc. #108 - Left

Approximate location of Backhoe Excavations
 Approximate Depth of Fill

Approximate location of Borings done by others

PROJECT NO. A71-1147
OCTOBER 22, 1971

FOUNDATION INVESTIGATION
PROPOSED
INDUSTRIAL BUILDING
12707 EAST LOS NIETOS ROAD
SANTA FE SPRINGS, CALIFORNIA

FOR

CAMPBELL PATTERN WORKS
12707 EAST LOS NIETOS ROAD
SANTA FE SPRINGS, CALIFORNIA 90670
ATT: MR. JACK ANDERSON

ADVANCED FOUNDATION ENGINEERING INC. / Consulting Foundation Engineers

October 22, 1971
Project A71-1147

Campbell Pattern Works
12707 East Los Nietos Road
Santa Fe Springs, California

Attention: Mr. Jack Anderson

Gentlemen:

Presented herewith is our report Preliminary Foundation Investigation conducted on the site of the proposed industrial building to be located at 12707 East Los Nietos Road, Santa Fe Springs, California.

The investigation was planned in accordance with the information furnished to us by your office. Column loads of 20 kips and continuous loads of 2,500 pounds per linear foot, both maximum live plus dead loads, were indicated.

Prudent evaluation of site conditions has been made with regard to the structural aspects of the proposed structure.

Respectfully submitted,

ADVANCED FOUNDATION ENGINEERING, INC.



Syed Z. Ahmad
Civil Engineer

SZA/mn

Distribution: Campbell Pattern Works (4)
John McKay Construction Company (1)

SCOPE

The purpose of this investigation was to determine the surface and subsurface soil conditions on the site and to obtain information on which to base recommendations for designing adequate foundations for the proposed building.

SITE LOCATION AND CONDITION

The location of the site for the proposed building is shown on Plate "A" of the Appendix. The ground is fairly level. Tall, dry weeds lie along the west side of the proposed building area, the only appreciable vegetation on the site.

The property was being used as a parking and storage area for truck-trailers and as a storage area for steel beams.

Two metal buildings, one at the west side of the lot and one at 2' west of the proposed building site, were the only structures on the site.

Approximately 1.5 feet of fill material was indicated by the test borings. In Boring 1, wooden timbers were encountered 4' to 6' deep. In Boring 2, oil content paints and brick remnants were encountered. The fill material is generally moderately expansive clayey silt material. The underlying natural soil was a silty clay with fine sand to 15.0 feet, with sandy soil to 20.0 feet.

No groundwater was encountered and no caving of the boring walls occurred during drilling operations on the date of drilling.

SITE LOCATION AND CONDITION - continued

The following is a brief description of the surroundings:

North of the property: Vacant lot, with tall dry weeds.

South of the property: Los Nietos Road; So. Calif. Edison Station.

East of the property: Lumber mill.

West of the property: Existing metal building; Dow Chemical outlet.

RECOMMENDATIONS

Based on the overall evaluation of site conditions and laboratory test results on undisturbed bag and soil samples, the following recommendations for the design of foundations are provided:

1. Considering the nature of foreign matter found in the fill material, it is recommended that the proposed building be supported on piers which penetrate through the existing fill and are embedded a minimum of three (3.1) feet into native soils, approximately from 9.0 to 12.5 feet deep. The allowable bearing pressure for the pier footings is 1,000 pounds per square foot.
2. To provide firm underlying support for the slab and continuous footings, all existing material in the building area should be excavated to a depth of one (1) foot over an area two (2) feet beyond the perimeter of the footings. Any root or other cavities found should be bladed clean of disturbed soil, compacted, and refilled with properly compacted soil.

RECOMMENDATIONS - continued

A coefficient of friction of 0.5 for concrete on compacted site material and a passive pressure of 250 pounds per square foot may be used in computing the resisting lateral forces.

The recommendations contained in this report reflect our best estimate of soil conditions based upon information obtained from the limited number of test borings performed. It is not to be construed as a warranty of the condition of the soil in other areas or at other depths. Should any unusual condition become apparent during grading or foundation construction, this office should be contacted for instructions prior to continuation of the work.

APPENDIX

The following Appendix contains the substantiating data and laboratory test results to complement the engineering evaluations and recommendations contained in the report.

Plate "A"	Plot Plan
Plate "B-1" and "B-2"	Boring Logs
Plate "C"	Load-Settlement Curves
Plate "D"	Direct Shear Tests
Plate "M"	Mechanical Analyses

SITE EXPLORATION

On October 15, 1971 field explorations were made by drilling two test borings at the approximate locations indicated on the attached plot plan, Plate "A". A truck-mounted rotary drilling rig equipped with an 18 inch diameter bucket-screw bit was used to advance the bore holes to depths of 15 to 20 feet from the existing grade.

Description of the soils encountered, depth of undisturbed cores, field density and firm moisture content are given on the log of borings for the test holes.

Undisturbed samples of soils were extracted in a barrel sampler with tapered cutting shoe. The undisturbed soil retained in 2.5 inch diameter by 1 inch rings within the sampler was tested in the laboratory to determine in-place density, moisture content, shear resistance and settlement characteristics.

Continuous observations of the materials encountered in the borings was recorded in the field. The soils were classified in the field by visual and textural examination and these classifications were supplemented by obtaining

SITE EXPLORATION - continued

bulk soil samples for future examination in the laboratory. All samples were secured in moisture-resistant bags as soon as taken to minimize the loss of field moisture while being transported to the laboratory and awaiting testing.

After the samples were visually classified in the laboratory, a testing program that would provide sufficient data for our analysis of the soils was established.

LABORATORY TESTS

Hydrometer and mechanical analyses were performed on various bulk soil samples to further check the visual classification and to determine the grain-size distribution of the soils. Mechanical analyses curves are presented on Plate "M".

Direct shear and consolidation tests were performed on selected undisturbed core samples to determine the shear strength and settlement characteristics of various soil samples.

LABORATORY TEST RESULTS

MAXIMUM DENSITY TEST RESULTS

The following Maximum Density Tests were conducted in accordance with ASTM D1557-71 method of test using 5 equal layers, 25 blows each layer, 10 pound hammer weight dropped in a 1/30 cubic foot mold.

<u>Test Hole No.</u>	<u>Depth, Ft.</u>	<u>Maximum Density,pcf</u>	<u>Optimum Moisture, %</u>
2	0.5-2.0	121.5	13.5

LABORATORY TEST RESULTS - continued

HYDROMETER ANALYSES RESULTS

Hole No.	Depth in Feet	% Sand	% Silt	% Clay
1	2.0	42.0	36.0	22.0
1	11.0-11.5	42.0	22.0	36.0
1	13.5-14.0	47.5	26.5	26.0
2	6.0-7.0	42.0	34.0	24.0
2	7.5-8.5	33.2	36.8	30.0
2	13.5-15.0	32.0	34.0	34.0

EXPANSION DETERMINATION

Expansion tests were performed on various soil samples to determine the swell characteristics of typical site materials and the following results were obtained for 60 pounds per square foot load.

Material Classification	Location	Maximum Density pcf	Opt. Moist %	Molded Dry Density	Molded Moisture Content	Expansion, % 60 psf Surcharge
Light tan - brown clayey silt with no sand (%)	T. 11, R. 2 0.5-2.0	121.5	13.5	107.8	14.3	5.6

PROCEDURE FOR EXPANSION TEST

A brief description of conducting the expansion test on typical site surface soils is described in the following paragraphs.

The test sample was thoroughly mixed with sufficient distilled water to bring the soil to approximately the optimum moisture content as determined by ASTM D1557-70 method of test.

PROPOSED BLDG.

LOS NIETOS RD

SCALE 1" = 40'

• DENOTES APPROX LOCATION OF TEST BORINGS

PLATE A


LOG OF BORINGS

WATER TABLE Not Encountered
 CAVING None
 DEPTH OF FILL 8.5'

PROJECT A71-1147
 TEST HOLE NO. 2
 DATE DRILLED October 15, 197


DEPTH IN FEET	SOIL	CLASSIFICATION (UNIFIED)	SYMBOL	DEPTH OF CORE SAMPLES	DRY DENSITY Pound / cu. ft.	MOISTURE PERCENT
				Ft.		
<u>TEST HOLE NO. 2</u>						
0.0-0.5	FILL - MISCELLANEOUS DEBRIS	- Brick dust, brick, and concrete fragments.				
0.5-8.5	FILL - CLAYEY SILT	- Light gray-brown with fine sand - lenses of silty clay and silty sand with alluvial appearance to 8.5' - oil smell between 4' and 5' - oil contaminated below 5.0' with silty clay lenses increasing and color grades to mottled dark gray-brown.	ML	0.5-2.0 2.0 3.0 4.0-5.0 5.0 6.0-8.5	* 104.0 103.4 * 101.6 *	9.9 14.9 16.3 16.3 17.7 13.0
8.5-15.0	NATURAL - SILTY CLAY	- Rust-brown, with fine sand - sand increases below 12' - color grades to light rust-brown below 13.5'.	CL	8.5-10.0 10.0 13.5- 15.0	* 116.8 *	12.4 14.3 16.3
15.0-18.0	CLAYEY FINE SAND	- Rust-brown - sand increases with depth.	SC	15.0	116.7	9.9
18.0-18.5	SILTY FINE SAND	- Light brown, ferrous stained ..	SM	18.0- 18.5	*	8.7
18.5-20.0	FINE SAND	- Light brown, with a trace of silt - trace of coarse sand apparent between 18.5' and 19.5'.	SP-SM	18.0- 20.0	*	4.2
*Indicates bulk sample taken for classification and moisture determination only.						

PLATE B - 2




ADVANCED FOUNDATION ENGINEERING INC.

CONSOLIDATION TEST RESULTS




DIRECT SHEAR TEST



MECHANICAL ANALYSIS CURVE

	FINE SILTY CLAY	CLAY	MEDIUM SAND	FINE SAND	VERY FINE SAND	FINE TO COARSE SILT	COARSE CLAY



PERCENT FINER BY WEIGHT

PLATE M